



USAID
FROM THE AMERICAN PEOPLE



INFRASTRUCTURE FOR BIODIVERSITY CONSERVATION IN KIDEPO VALLEY NATIONAL PARK

BOOK OF DRAWINGS

Construction of Major and Minor Low Water Stream Crossings Structures (LWSC) at "Kidepo river."

Beneficiary : UGANDA WILDLIFE AUTHORITY

Funder: United States Agency for International Development (USAID)




**Prepared by: USAID / Uganda Architect & Engineering Design and Construction Management Services
Implemented by: MBW Consulting Ltd. and DT Global. USA**

LIST OF DRAWINGS AND GENERAL NOTES

**INFRASTRUCTURE FOR BIODIVERSITY CONSERVATION IN KIDEPO VALLEY NP - LOW WATER STREAM CROSSINGS (LWSC)
LIST OF DRAWINGS**




Drawing Description	Drawing No.	Revision
<u>LIST OF DRAWINGS AND GENERAL NOTES</u>		
List of General Notes_ General Notes 1	906-01-DWG-GN-001	
List of General Notes_ General Notes 2	906-01-DWG-GN-002	
List of General Notes_ General Notes 3	906-01-DWG-GN-003	
<u>KIDEPO LOW WATER STREAM CROSSINGS (LWSC)</u>		
<u>LOCATION MAP</u>		
Location Map _LWSC	906-01-DWG-C-GD-001	
<u>TYPICAL DRAWINGS OF LWSC AND APPROACH ROADS</u>		
LWSC # Approach Roads : Typical Approach Road # LWSC Schematic Diagram	906-01-DWG-C-TS-001	
LWSC # Approach Roads : Typical River Training Cross Sections # LWSC Section 1	906-01-DWG-C-TS-002	
LWSC # Approach Roads : Typical Approach Road and LWSC Section 2 # 3	906-01-DWG-C-TS-003	
<u>KIDEPO MAJOR LWSC</u>		
<u>PLAN VIEW</u>		
Plan View : Plan View of Kidepo Major LWSC	906-01-DWG-D-P-01	
Plan View : Plan View of Kidepo Minor LWSC	906-01-DWG-D-P-02	
Plan View : Kidepo Major LWSC Test Pit Locations	906-01-DWG-D-P-03	
Plan View : Kidepo Minor LWSC Double Culvert Locations	906-01-DWG-D-P-04	
<u>PLAN AND PROFILE OF LWSC AND APPROACH ROADS</u>		
Plan # Longitudinal Profile : Kidepo LWSC # Approach Roads	906-01-DWG-C-PP-001.1	
Plan # Longitudinal Profile : Kidepo LWSC River Profile	906-01-DWG-C-PP-001.2	
LWSC # Approach Roads Detail 01 : Kidepo LWSC	906-01-DWG-C-DR-001.3	
LWSC # Approach Roads : Structural Plan and Longitudinal Section for Kidepo	906-01-DWG-C-DR-001.4	
LWSC # Approach Roads : Structural Sectional Details for Kidepo LWSC	906-01-DWG-C-DR-001.5	

Drawing Description	Drawing No.	Revision
<u>KIDEPO MINOR LWSC</u>		
<u>PLAN AND PROFILE OF LWSC AND APPROACH ROADS</u>		
Plan # Longitudinal Profile : Kidepo Minor LWSC # Approach Roads	906-01-DWG-C-PP-002.1	
Plan # Longitudinal Profile : Kidepo Minor LWSC River Protection Details	906-01-DWG-C-PP-002.2	
LWSC # Approach Roads Detail 02 : Kidepo Minor LWSC	906-01-DWG-C-PP-002.3	
LWSC # Approach Roads : Plan and Sectional views for Kidepo Minor LWSC (Culvert 2+761.15)	906-01-DWG-C-DR-002.3A	
LWSC # Approach Roads : Plan and Sectional views for Kidepo Minor LWSC (Culvert 2+798.01)	906-01-DWG-C-DR-002.3B	
LWSC # Approach Roads : Plan and Sectional views for Kidepo Minor LWSC (Culvert 2+828.27)	906-01-DWG-C-DR-002.3C	
LWSC # Approach Roads : Sectional Details for Kidepo Minor LWSC Culvert	906-01-DWG-C-DR-002.4A	
LWSC # Approach Roads : Sectional Details for Kidepo Minor LWSC Gabion Box	906-01-DWG-C-DR-002.4B	
LWSC # Approach Roads : Sectional Details for Kidepo Minor LWSC Pavement	906-01-DWG-C-DR-002.4C	
LWSC # Approach Roads : Structural Plan and Longitudinal Section for Kidepo Minor LWSC	906-01-DWG-C-DR-002.5B	
LWSC # Approach Roads : Structural Plan and Longitudinal Section for Kidepo Minor LWSC	906-01-DWG-C-DR-002.5C	
LWSC # Approach Roads : Structural Sectional Details for Kidepo Minor LWSC	906-01-DWG-C-DR-002.6	
<u>STANDARD DRAWINGS</u>		
LWSC # Approach Roads : Culvert Installation Details	906-01-DWG-C-SD-001	
LWSC # Approach Roads : Standard Road Signs	906-01-DWG-C-SD-002	
LWSC # Approach Roads : Road Signs Mounting Details	906-01-DWG-C-SD-003	
LWSC # Approach Roads : Major LWSC Standard Roads Signs Location	906-01-DWG-C-SD-004	
LWSC # Approach Roads : Minor LWSC Standard Roads Signs Location	906-01-DWG-C-SD-005	
<u>COMPARISON BETWEEN DESIGNED # OPENED UP LONGITUDINAL ROAD ALIGNMENT</u>		
LWSC # Approach Roads : KMO+000.000 to KM1+609.461	906-01-DWG-D-C5-002	
LWSC # Approach Roads : KMO+000.000 to KM6+766.532	906-01-DWG-D-C5-002	
LWSC # Approach Roads : KM1+609.461 to KM3+218.922	906-01-DWG-D-C5-003	
LWSC # Approach Roads : KM3+218.922 to KM4+828.383	906-01-DWG-D-C5-004	
LWSC # Approach Roads : KM4+828.383 to KM6+766.532	906-01-DWG-D-C5-005	

CONSULTANT:  Plot 107 Kibi Road, Kampala, P.O. Box 1073, Kampala, Tel: +256 312 210001 Email: info@m-e.com.ug	FUNDER:  UNITED STATES OF AMERICA	CLIENT:  Uganda Wildlife Research Institute P.O. Box 200, Kampala, Tel: +256 312 210011, 2011	PROJECT NAME: USAID / Uganda Architect & Engineering Design and Construction Management Services	DESIGNED BY: ENC. SS DRAWN BY: BK	REVISED: _____ DATE: _____ REVISED: _____ DATE: _____ REVISED: _____ DATE: _____ REVISED: _____ DATE: _____	SCALE: _____ AS NOTED	SHEET NO: _____ TOTAL SHEETS: _____
			ACTIVITY NAME: Initiative for Biodiversity Conservation in Kidepo Valley National Park	CHECKED BY: ENC. SS	APPROVED BY: _____ DATE: _____ APPROVED BY: _____ DATE: _____	DESCRIPTION OF REVISION BY: _____	COPYRIGHT RESERVED

GENERAL NOTES 1: IN CASE OF DISCREPANCIES BETWEEN THE GENERAL NOTES/DETAILS AND ANY NOTES/DETAILS ON INDIVIDUAL DRAWINGS, THE NOTES / DETAILS ON EACH DRAWING TAKE PRECEDENCE

1. GENERAL	2. APPROACH ROADS
<p>1.1. THE STRUCTURES AND THEIR COMPONENTS ARE DESIGNED ACCORDING TO THE CRITERIA INDICATED BY THE REGULATIONS BELOW. ALL THE REGULATIONS BELOW ARE IN THE LATEST VERSIONS:</p> <p>INTERNATIONAL DESIGNS CODES.</p> <p>EN 1990 - 'Eurocode 0: Basis of Structural design'</p> <p>EN 1991 - 'Eurocode 1: Actions on Structures'</p> <p>EN 1992 - 'Eurocode 2: Design of Concrete Structures'</p> <p>EN 1993 - 'Eurocode 3: Design of Steel Structures'</p> <p>EN 1997 - 'Eurocode 7: Geotechnical design'</p> <p>EN 1998 - 'Eurocode 8: Design of structures for earthquake resistance'</p> <p>IN HARMONISATION OF PROFESSIONAL PRACTICE AND ENSURING APPROPRIATE LEVELS OF SAFETY, HEALTH AND ECONOMY WITH DUE CONSIDERATION OF THE OBJECTIVES CONDITIONS AND NEED OF THE CONSTRUCTION THE STANDARD SPECIFICATION FOR BUILDING WORKS FOR MINISTRY OF WORKS HOUSING AND COMMUNICATIONS SHOULD BE APPLIED HAND IN HAND WITH THE NAMED STANDARDS.</p> <p>1.3. DIMENSIONS ARE NOT TO BE SCALED FROM THE DRAWINGS. FOLLOW WRITTEN DIMENSIONS ONLY.</p> <p>1.4. ALL DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE RELEVANT ARCHITECTURAL DRAWINGS, SPECIFICATIONS, BILLS OF QUANTITIES AND ALL OTHER RELEVANT DOCUMENTS. DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO THE ENGINEER PRIOR TO COMMENCEMENT OF ANY WORK.</p> <p>1.5. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCEMENT OF WORKS AND ANY DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER BEFORE EXECUTION.</p> <p>1.6. ALL CONCRETE SIZES AND LEVELS ARE FOR STRUCTURAL ELEMENTS UNLESS OTHERWISE NOTED.</p> <p>1.7. NO HOLES OR CHASES ARE PERMITTED IN THE CONCRETE MEMBERS OTHER THAN AS DETAILED OR UNLESS APPROVED BY THE ENGINEER.</p> <p>1.8. CONSTRUCTION JOINTS SHALL BE LOCATED TO THE APPROVAL OF THE ENGINEERS.</p> <p>1.9. ANY DAMAGE CAUSED TO ANY CIVIL / STRUCTURAL WORK SHALL BE REINSTATED TO ITS ORIGINAL CONDITION WITH NO COST IMPLICATION TO THE CLIENT.</p>	<p>2.1. THE APPROACH ROADS AND THEIR COMPONENTS ARE DESIGNED ACCORDING TO THE CRITERIA INDICATED BY THE FOLLOWING ROAD DESIGN MANUALS AND STANDARDS FROM MINISTRY OF WORKS AND TRANSPORT:</p> <p>Volume 1 - 'Geometric design'</p> <p>Volume 2 - 'Drainage design manual "</p> <p>Volume 3 - 'Part I: Flexible Pavement design manual "</p> <p>Volume 3 - 'Part II: Rigid Pavement design manual'</p> <p>Volume 3 - 'Part I: Gravel Roads design manual'</p> <p>Volume 3 - 'Part IV: Pavement Rehabilitation design manual'</p> <p>Volume 4 - 'Bidge design manual'</p>

<p>CONSULTANT:</p>  <p>Plot 107 New Road, Kampala Uganda Road Construction Ltd. P.O. Box 10000 00101 Kampala UGANDA Email: info@mbiconsulting.com</p>	<p>FUNDER:</p>  <p>USAID ABOUT THE AMERICAN PEOPLE</p>	<p>CLIENT:</p>  <p>Uganda Wildlife Authority P.O. Box 10000 Kampala UGANDA</p>	<p>PROJECT NAME: USAID /Uganda Architect & Engineering Design and Construction Management Services</p> <p>ACTIVITY NAME: Infrastructure for Biodiversity Conservation in Kidepo Valley National Park</p> <p>DRAWING DESCRIPTION: UASC LIST OF GENERAL NOTES LIST OF GENERAL NOTES 1</p>	<p>DESIGNED BY: DATE: / /</p> <p>DRAWN BY: DATE: / /</p> <p>CHECKED BY: DATE: / /</p> <p>APPROVED BY: DATE: / /</p>	<p>REVISION:</p> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION OF REVISION</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	NO.	DATE	DESCRIPTION OF REVISION	BY													<p>PROJECT SEAL:</p> <p>SCALE: As Noted</p> <p>STATUS: REVISED DESIGN</p> <p>DATE: 2024.04.22</p> <p>DRAWING NUMBER: 906-01-DMC-CH-001</p> <p>COPYRIGHT RESERVED</p>
NO.	DATE	DESCRIPTION OF REVISION	BY																			

GENERAL NOTES 2:

IN CASE OF DISCREPANCIES BETWEEN THE GENERAL NOTES/DETAILS AND ANY NOTES/DETAILS ON INDIVIDUAL DRAWINGS, THE NOTES / DETAILS ON EACH DRAWING TAKE PRECEDENCE

3. CONCRETE

- 3.1 UNLESS OTHERWISE SPECIFIED, ALL STRUCTURAL CONCRETE MIX TO BE OF GRADE 30
- 3.2 ALL CONCRETE STRENGTHS ARE 28 DAYS CUBE STRENGTH.
- 3.3 UNLESS OTHERWISE SPECIFIED, A LAYER OF 50mm THICK GRADE 15 CONCRETE TO BE PROVIDED BELOW ALL REINFORCED CONCRETE STRUCTURES IN CONTACT WITH THE GROUND.
- 3.4 UNLESS OTHERWISE SPECIFIED, ALL LEAN CONCRETE MIX TO BE OF GRADE 15.
- 3.5 MAXIMUM AGGREGATE SIZE SHALL BE 20mm.
- 3.6 CURING OF CONCRETE
 - EXPOSED CONCRETE SURFACES SHOULD BE COVERED WITH DAMP ABSORBENT MATERIAL AFTER PLACING CONCRETE.
 - THEY SHOULD BE KEPT CONTINUOUSLY WET BY FREQUENT SPRAYING OF WATER.
 - IN COLUMNS CURING SHOULD BE STARTED IMMEDIATELY AFTER REMOVAL OF FORMWORK.
 - MINIMUM PERIOD OF CURING IS 4 DAYS.

3.7 REMOVAL OF SHUTTERING:

STRUCTURAL ELEMENTS	MINIMUM PERIOD
VERTICAL FORMWORK TO COLUMNS AND WALLS	24 HOURS
SOFFIT FORMWORK TO SLABS	10 DAYS
SOFFIT FORMWORK TO BEAMS	10 DAYS
PROPS TO BEAMS	14 DAYS

3.8 GRADE OF CONCRETE

CONCRETE	CUBE/CYLINDER	CHARACTERISTIC STRENGTH, N/mm ²
BLINDING SCREED / LEVELING CONCRETE	C15, (C12)	15
MASS CONCRETE	C20, (C15)	20
STRUCTURAL CONCRETE	C30, (C25)	30

4. REINFORCEMENT

- 4.1. UNLESS OTHERWISE SPECIFIED, ALL STEEL REINFORCEMENT BARS AND WELDED STEEL FABRIC REINFORCEMENTS (WSFR) SHALL COMPLY WITH THE REQUIREMENTS OF EUROCODE 2.
- 4.2. 'R' DENOTES MILD STEEL OF YIELD STRENGTH = 250 N/MM²
- 4.3. 'T' DENOTES HIGH TENSILE DEFORMED BARS (TYPE 2) OF YIELD STRENGTH = 460 N/MM²
- 4.4. CONCRETE COVER TO OUTERMOST REINFORCEMENT, INCLUDING LINKS, SHALL BE AS FOLLOWS :

STRUCTURAL ELEMENTS	IN CONTACT WITH GROUND	OTHER
SLABS	50 mm	20 mm
BEAMS	50 mm (TOP) 50 mm (SIDE & BOT.)	25 mm
COLUMNS	50 mm	40 mm
FOOTINGS	50 mm	--


- 4.5. WELDING OF REINFORCEMENT WILL NOT BE PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER.

BAR SIZE (mm)	6	10	12	16	20	25	32
T = HIGH YIELD STEEL	-	500	600	800	1000	1200	1330
R = MILD STEEL	300	-	-	-	-	-	-

- 4.6. ALL BARS SHALL BE CUT AND BENT TO CONFORM TO EUROCODE 2. UNLESS OTHERWISE STATED IN THE DRAWINGS, THE MINIMUM LAP LENGTH FOR REINFORCEMENT SHALL BE 50 TIMES THE DIA. OF SMALLER BAR IN THE LAP.

BAR SIZE (mm)	A	B	C
T32	1100	-	900
T25	850	-	700
T20	700	-	330
T16	330	450	450
T12	400	400	400
T10	-	300	-

- 4.7. ALL BARS AT THE ENDS OF THE BEAMS WHERE THE BEAM IS NO MORE CONTINUOUS SHALL BE ANCHORED EITHER STRAIGHT OR BENT (DEPENDING ON THE WIDTH OF THE SUPPORT) AS SHOWN BELOW. THESE SHALL NOT BE USED IN CANTILEVERED BEAMS OR SLABS. THE ACTUAL DESIGN DRAWING SHALL BE STRICTLY ADHERE TO.



PROJECT NAME: USAID / Uganda Architect & Engineering Design and Construction Management Services
 ACTIVITY NAME: Infrastructure for Biodiversity Conservation in Kidepo Valley National Park
 DRAWING DESCRIPTION: LVSC - LIST OF GENERAL NOTES
 GENERAL NOTES 2

DESIGNED BY: [Blank]
 DRAWN BY: [Blank]
 CHECKED BY: [Blank]
 APPROVED BY: [Blank]

REV. NO.	DATE	DESCRIPTION OF REVISION	BY




SCALE: As Noted
 STATUS: REVISED DESIGN
 DATE: 2024-04-22
 DRAWING NUMBER: 006-01-DMC-04-002
 SHEETS: 13
 PAGES: 13
 COPYRIGHT RESERVED

GENERAL NOTES 3: IN CASE OF DISCREPANCIES BETWEEN THE GENERAL NOTES/DETAILS AND ANY NOTES/DETAILS ON INDIVIDUAL DRAWINGS, THE NOTES / DETAILS ON EACH DRAWING TAKE PRECEDENCE



5. NOTES ON LOW WATER STEAM CROSSINGS

IN THE CONSTRUCTION OF THE LOW WATER STREAM CROSSING, THE FOLLOWING MAJOR DESIGN MODIFICATIONS WERE CONSIDERED TO OVERCOME THE PRESENT ENCUMBRANCES EXPERIENCED AT THE SITES:

- 5.1 UNLESS UNDER-SCOURING/CUTTING OF THE PAVEMENT HAS BEEN PREVENTED BY INTRODUCING EDGE BEAMS ON TOP OF GABION MATTRESSES FILLED WITH STONES.
- 5.2 MINIMIZING OR AVOIDING THE DAMMING EFFECT WHICH CREATES SILTING NEAR THE DRIFT UPSTREAM HAS BEEN ACHIEVED BY ENABLING THE DRIFT'S VERTICAL ALIGNMENT TO CREATE A SELF-CLEANING EFFECT AT THE CROSSING. THIS SHOULD BE DONE HAVING IN MIND THAT LWSC ARE DESIGNED FOR OVERTOPPING WITH FLOODWATER AND CONSEQUENTLY HAVE AN INHERENT VERTICAL DIP CHARACTERISTIC. THE APPROACH ROADWAY SHALL BE AT THE NORMAL GROUND LEVEL ON THE STREAM BANKS, WHEREAS THE LOW POINT OF THE CROSSING MAY BE MUCH CLOSER TO THE NORMAL WATER FLOW SURFACE THAN A TYPICAL CULVERTED DESIGN. IT SHOULD HOWEVER BE NOTED THAT THIS SUDDEN DIP IN THE VERTICAL ALIGNMENT IS INCONSISTENT WITH THE DRIVER'S EXPECTATIONS OF A PUBLIC HIGHWAY PROFILE. THAT IS WHY PROPER SIGNAGE SHOULD BE PUT IN PLACE FOR SAFETY. FOR AN EFFECTIVE SELF-CLEANING SYSTEM, IT IS NECESSARY TO TRAIN THE RIVER INCLUDING DREDGING 100 M UPSTREAM AND DOWNSTREAM OF THE DRIFT.
- 5.3 TO CREATE A GOOD BASE/FOUNDATION FOR THE DRIFT AND AT THE SAME TIME REDUCE THE VERTICAL GRADE OF THE ROAD AT THE CROSSING, IT MAY BE NECESSARY TO FILL THE RIVERBED WITH COMPACTED APPROVED GRAVEL AND HARDCORE IN LAYERS.
- 5.4 THE DRIFT SHOULD HAVE ANCHORAGE PREFERABLY AT THE RIVER BANK IN FORM OF A STABLE ROCK TO PREVENT IT FROM BEING WASHED AWAY BY THE RIVER FLOW. IN CASE A STABLE ROCK IS NOT AVAILABLE, A REINFORCED CONCRETE ANCHORAGE WILL BE PROPOSED.

CONSULTANT:  P.O. Box 1000 Kampala Uganda Tel: +256 471 222222 Email: info@mbm.co.ug	FUNDER:  USAID FROM THE AMERICAN PEOPLE	CLIENT:  UWA Uganda Wildlife Authority P.O. Box 1000 Kampala Uganda Tel: +256 471 222222 Email: info@uwa.or.ug	PROJECT NAME: USAID / Uganda Architect & Engineering Design and Construction Management Services	DESIGNED BY: DATE:	APPROVED BY: DATE:	REVISED BY: DATE:	DESCRIPTION OF REVISION	BY	NUMBER OF REVISION	SCALE: As Noted	DATE: 2024-04-22	PAGES: 13	DRAWING NUMBER: DWG-01-DWC-CH-003	COPYRIGHT RESERVED
			ACTIVITY NAME: Infrastructure for Biodiversity Conservation in Kidepo Valley National Park							CHECKED BY: DATE:	APPROVED BY: DATE:	REVISED BY: DATE:	DESCRIPTION OF REVISION	BY

LOCATION MAP



Legend

- Water Catchments
- River Outlets
- LWSC Locations
- District Boundaries
- Rivers
- River Types
- Major
- Minor
- Waterbodies
- Coast Types
- Open Water
- Swamp

12 Kilometers

0 3 6

Coordinates System: Air; 1980 UTM Zone 38N
 Projection: Transverse Mercator
 False Easting: 500,000.0000
 False Northing: 0.0000
 Central Meridian: 33.0000
 Scale Factor: 0.9996
 Latitude Of Origin: 0.0000
 Units: Meter

CONSULTANT: MW CONSULTING

FINDER: USAID FROM THE AMERICAN PEOPLE

CLIENT: Uganda Wildlife Authority
 UWA

PROJECT NAME: USAID / Uganda Architect & Engineering Design and Construction Management Consulting Services

ACTIVITY NAME: LOW WATER STREAM CROSSINGS AND WATER CATCHMENTS AT KARENGA NATIONAL PARK.

DRAWING DESCRIPTION: GENERAL DRAWINGS LOCATION MAP

REV. No	DATE	DESCRIPTION OF REVISION	BY

DESIGNED BY: SRO
DRAWN BY: JJK
CHECKED BY: BK
APPROVED BY: UT

ENGINEER'S SEAL:

AS NOTED

STATUS: DETAILED DESIGN



DATE: MAR 2023

PROJECT NUMBER: 906-01-LWC-D-00-001

REF. NO.: 906-01-LWC-D-00-001

COPYRIGHT RESERVED

TYPICAL DRAWINGS OF
LWSC AND APPROACH
ROAD



SCHEMATIC DIAGRAM OF LWSC

LWSC	Splash apron (m)	L1 (m)	L2 (m)	L3 (m)
Kidepo (Major)	4.00	40.00	40.00	-

CONSULTANT: Plot 107 Kamp Road, Kampala Uganda Tel: +256 312 222 222 Email: info@mbm.co.ug	FUNDER: UNITED STATES OF AMERICA FOR THE AMERICAN PEOPLE	CLIENT: Uganda Wildlife Authority P.O. Box 100, Kampala Uganda Tel: +256 312 222 222 Email: info@uwa.or.ug	PROJECT NAME: USAID / Uganda Architect & Engineering Design and Construction Management Services	DESIGNED BY: DATE:	ENGINEER'S SEAL: NAME:	SCALE: As Noted
			ACTIVITY NAME: Infrastructure for Biodiversity Conservation in Kidepo Valley National Park	DRAWN BY: DATE:	CHECKED BY: DATE:	STATUS: REVISED DESIGN 2024.04.22 A3
DRAWING DESCRIPTION: LWSC AND APPROACH ROADS Kidepo Valley National Park, Uganda			APPROVED BY: DATE:	REVISION: NO. DATE DESCRIPTION OF REVISION	BY:	COPYRIGHT RESERVED